



1. DOWELLED JOINT TO BE PLACED EVERY 15m AT BOTH SIDES OF DRIVEWAYS AND WHERE PEDESTRIAN LAYBACKS ARE CONSTRUCTED.
2. CONCRETE TO BE 25MPa AT 28 DAYS (BROOM FINISH) WITH F72 REINFORCEMENT PLACED 40mm FROM TOP SURFACE. 10mm DEFORMED BARS TO BE DOWELLED A MIN 150mm INTO EXISTING CONCRETE, AND 150mm INTO PROPOSED CONCRETE AT 450mm CENTRES

CITY OF BALLARAT

CONCRETE FOOTPATH
WITH SPOON DRAIN
IN NEW SUBDIVISIONS

ALTERATION TO CONCRETE THICKNESS	SEPT 10	Approved by:	
UPDATE OF NOTES AND DOWELLED JOINT	OCT 11		
No. AMENDMENTS	DATE	Date:	

SCALE:
NOT TO SCALE

SHEET 1 OF 1

DRAWING NO:
SD-K4-2

