





NOTES:
 THE RAMP AND SLOPING SIDES SHOULD BE SLIP RESISTANT. USE BROOM SURFACE FINISH. MINIMUM CONCRETE DEPTH 150mm.
 REFER TO A.S.1428.1 AND A.S.1428.4 FOR PROFILE AND CORRECT PLACEMENT OF TGIS. IF CONFLICT OCCURS BETWEEN COUNCIL'S STANDARD DWG AND AUSTRALIAN STANDARDS, DEFER TO AUSTRALIAN STANDARD.
 TACTILES ARE TO BE OF AN APPROVED CERAMIC MATERIAL. (UNLESS OTHERWISE SPECIFIED BY CONTRACT SUPERVISOR)
 TACTILE COLOR MUST BE IVORY, WITH A CERTIFICATE OF LUMINANCE COMPLIANCE (TO AS1428 IN WET AND DRY CONDITIONS) TO BE SUPPLIED BY THE MANUFACTURER. (UNLESS OTHERWISE SPECIFIED BY THE CONTRACT SUPERVISOR).
 MANUFACTURER MUST SUPPLY SPECIFICATION FOR INSTALLATION OF TACTILES. INSTALLATION MUST BE IN ACCORDANCE WITH THIS SPECIFICATION. (UNLESS OTHERWISE SPECIFIED BY THE CONTRACT SUPERVISOR).



CITY OF BALLARAT

No.	AMENDMENTS	DATE	Approved by:
1	ADDED TACTILE INDICATORS	DEC 00	
2	CHANGED NOTES	APR 04	
3	CHANGED CONSTRUCTION JOINTS	NOV 11	
			Date:

PEDESTRIAN KERB
 RAMP DETAIL
 WITH TACTILE INDICATORS



CITY OF BALLARAT

SCALE:
 NOT TO SCALE

SHEET 1 OF 4
 DRAWING NO:
 SD-C4-1